

**Town of Truro
Health & Conservation
24 Town Hall Rd
508-349-7004 ex. 131**

Memo

To: Disposal Works Installers
From: Truro Health & Conservation Department
CC:
Date: June 21, 2018
Re: Septic System Install Inspection Requirements

- Orange card as-builts should be available on site or dropped off prior to inspection.
 - Unless a partial has been scheduled, the system should be ready for backfill.
 - Watertight risers shall be built up and installed according to plans. Risers shall not be more than 3' tall.
 - Cleanouts are required by code on the building sewer where the pipe changes direction/elevation and for every 100' of pipe.
 - If the install is an upgrade, the old system/cesspools shall be filled and compacted.
 - Water shall be on site to test distribution box.
 - Covers shall be open to allow inspection. If necessary, please be onsite to open covers.
-
- **TIGHT TANKS:** Septage Hauler's name and phone number must be sited on the alarm.